

DESIGN							
	WALL TYPE	W27	W28	W29	W32	W33	W35
	FIRE RATING	1 HR RATED	1 HR RATED		2 HR RATED		2 HR RATED SHAFT
	UL DESIGN	UL 263 DESIGN U465	UL 263 DESIGN U419 STC 56-WEAL TL09-568/ TL09-569		UL 263 DESIGN U419		U438
	MATERIAL (READ FROM LEFT TO RIGHT)	5/8" TYPE "X" GWB ON BOTH SIDES OF 6" METAL STUDS, @ 16" O.C. W/ R-19 INSULATION	(UNIT SIDE) TWO LAYERS OF 5/8" TYPE "X" GWB 20 GA 6" MTL. STUDS @ 24" O.C. 6" UL LISTED FIBERGLASS INSULATION. TWO LAYERS OF 5/8" TYPE "X" GWB (UNIT SIDE)	5/8" GWB ON BOTH SIDES OF 6" METAL STUDS @ 16" O.C.	TWO (2) LAYERS OF 5/8" GWB (TYPE X) ON BOTH SIDES OF 6" MTL STUDS @ 16" O.C. & R-19 INSULATION	5/8" DENSHEILD ON 20GA-3 5/8" MTL STUDS @ 16" O.C. ON BOTH SIDES OF PIPE CHASE	6" DEEP "C-H" 25GA GALV. MTL STUDS @ 16" O.C. MAX. WITH 1" THICK WALLBOARD LINER WITHIN THE "H" PORTION OF THE STUD AND 2 LAYERS OF 5/8" GWB APPLIED TO FACE OF "C" PORTION OF THE STUD.
ALTERNATE FINISHES			W29A W30 W30A W31	W32A	W34		
FINISHES	ALL WALLS ARE TO BE PREPARED TO RECEIVE FINISH - REFER TO FINISH SCHEDULE	ALL WALLS ARE TO BE PREPARED TO RECEIVE FINISH - REFER TO FINISH SCHEDULE	ALL WALLS ARE TO BE PREPARED TO RECEIVE FINISH - REFER TO FINISH SCHEDULE	ALL WALLS ARE TO BE PREPARED TO RECEIVE FINISH - REFER TO FINISH SCHEDULE	ALL WALLS ARE TO BE PREPARED TO RECEIVE FINISH - REFER TO FINISH SCHEDULE	ALL WALLS ARE TO BE PREPARED TO RECEIVE FINISH - REFER TO FINISH SCHEDULE	
NOTES	• CONTRACTOR SHALL ADD DENSHEILD AT ALL WET AREAS. (DENSHEILD TYPE X AT FIRE RATED ASSEMBLY). • 20 GA. MIN. METAL STUDS AT 16" O.C. SHALL BE PROVIDE AT ALL CABINET AND WALL HUNG FIXTURE & STRUCT. WALLS AS PER FBC. • PROVIDE FIRE RATED SEALANT AS NEEDED PER UL DESIGN. • CONTRACTOR SHALL STRICTLY ADHERE TO UL DESIGN STANDARDS AND LABEL WALL ACCORDING TO FIRE RATINGS AS PER FBC. • NO SOUND BLANKET AT UNIT ENTRY DOOR STC 53 MIN. REQUIRED.	• CONTRACTOR SHALL ADD DENSHEILD AT ALL WET AREAS. (DENSHEILD TYPE X AT FIRE RATED ASSEMBLY). • 20 GA. MIN. METAL STUDS AT 16" O.C. SHALL BE PROVIDE AT ALL CABINET AND WALL HUNG FIXTURE & STRUCT. WALLS AS PER FBC. • PROVIDE FIRE RATED SEALANT AS NEEDED PER UL DESIGN. • CONTRACTOR SHALL STRICTLY ADHERE TO UL DESIGN STANDARDS AND LABEL WALL ACCORDING TO FIRE RATING AS PER FBC. • NO SOUND BLANKET AT UNIT ENTRY DOOR	• CONTRACTOR SHALL ADD DENSHEILD AT ALL WET AREAS. (DENSHEILD TYPE X AT FIRE RATED ASSEMBLY). • 20 GA. MIN. METAL STUDS AT 16" O.C. SHALL BE PROVIDE AT ALL CABINET AND WALL HUNG FIXTURE AREA. CROSS BRACING SHALL BE AS REQUIRED. • PROVIDE CROSS BRACING AT GRAB BAR LOCATIONS. • PROVIDE FIRE RATED SEALANT AS NEEDED PER UL DESIGN. • CONTRACTOR SHALL STRICTLY ADHERE TO UL DESIGN STANDARDS AND LABEL WALL ACCORDING TO FIRE RATINGS AS PER FBC. STC 50 MIN. REQUIRED.	• CONTRACTOR SHALL ADD DENSHEILD AT ALL WET AREAS IN LIEU OF GWB AND 25 GA. MIN. METAL STUDS AT 16" O.C. • 20 GA. MIN. METAL STUDS AT 16" O.C. SHALL BE PROVIDE AT ALL CABINET AND WALL HUNG FIXTURE AREA. CROSS BRACING SHALL BE AS REQUIRED. • PROVIDE CROSS BRACING AT GRAB BAR LOCATIONS. • PROVIDE FIRE RATED SEALANT AS NEEDED PER UL DESIGN. • CONTRACTOR SHALL STRICTLY ADHERE TO UL DESIGN STANDARDS AND LABEL WALL ACCORDING TO FIRE RATINGS AS PER FBC. STC 50 MIN. REQUIRED.	• CONTRACTOR SHALL PROVIDE DENSHEILD AT ALL WET AREAS IN LIEU OF GWB AND 20 GA. MIN. METAL STUDS AT 16" O.C. • 20 GA. MIN. METAL STUDS AT 16" O.C. SHALL BE PROVIDE AT ALL CABINET AND WALL HUNG FIXTURE AREA. CROSS BRACING SHALL BE AS REQUIRED. • PROVIDE CROSS BRACING AT GRAB BAR LOCATIONS. • PROVIDE FIRE RATED SEALANT AS NEEDED PER UL DESIGN. • CONTRACTOR SHALL STRICTLY ADHERE TO UL DESIGN STANDARDS AND LABEL WALL ACCORDING TO FIRE RATINGS AS PER FBC. STC 50 MIN. REQUIRED.	• REFER TO UL DESIGN GUIDE LINE & STRICTLY ADHERE TO REQUIREMENTS	
INSULATION NOTE: WALLS WITH PENETRATIONS REQUIRE THAT INSULATION BE CAREFULLY CUT TO FIT AROUND OUTLETS, JUNCTION BOXES AND OTHER IRREGULARITIES.							
GENERAL WALL NOTES				STANDARD CODE REQUIREMENTS			
1. CONTRACTOR SHALL COORDINATE ALL WALL TRADES PRIOR TO LAYING OUT WALLS. 2. COORDINATE ALL PLUMBING LINES AND WALL THICKNESS PRIOR TO COMMENCING. 3. WALLS SHALL BE LEVEL AND PLUMB. 4. FIRE RATED/SMOKE PARTITIONS SHALL BE NOTED AS PER FBC 2017. THESE WALLS SHALL CONFORM TO SECTIONS 708, 709 AND 710 OF THE FBC 2017 5. ALL PENETRATIONS SHALL BE FIRE RATED TO MATCH WALLS AND SHALL COMPLY W/SECTION 714 OF THE FBC 2017. 6. UL RATED ASSEMBLIES SHALL BE NOTED. APPROVED EQUAL SHALL MATCH FIRE/SMOKE RATING INDICATED ON DRAWINGS. 7. CONTRACTOR SHALL COORDINATE STUCCO FINISHES FOR EXTERIOR OF BUILDING PRIOR TO COMMENCING ANY WORK.				1. PROVIDE WATERPROOF GWB AT ALL WET AREAS. 2. TUB AND SHOWER AREAS SHALL HAVE NON-ABSORBENT SURFACE UP TO 70" ABOVE THE DRAIN INLET. 3. TUBS AND SHOWERS SHALL HAVE WATERPROOF JOINTS BETWEEN TUB AND ADJACENT WALLS. 4. HORIZONTAL BRACING BETWEEN STUDS SHALL BE PROVIDED AS NEEDED. 5. MIN. 20 GA. METAL STUDS SHALL BE USED FOR PARTITIONS WHERE FIXTURES OR CABINETRY SHALL BE INSTALLED. 6. REFER TO LIFE SAFETY DRAWINGS FOR ADDITIONAL FIRE RATED WALLS AND PARTITIONS NOTES AND LOCATIONS. WHERE DISCREPANCIES ARE NOTED, NOTIFY ARCHITECT PRIOR TO COMMENCING ANY WORK. 7. ALL INSULATION MATERIAL SHALL HAVE A FLAME SPREAD INDEX OF 25 MAX. & SMOKE - DEVELOPED INDEX OF 450 MAX.			
8. FIRE WALLS, FIRE BARRIERS, FIRE PARTITIONS OR ANY OTHER WALL REQUIRED TO HAVE PROTECTIVE OPENINGS SHALL BE PERMANENTLY IDENTIFIED AS PER FBC 2017 703.7. SUCH IDENTIFICATION SHALL BE ABOVE ANY DECORATIVE CEILING AND CONCEALED SPACES AND SHALL BE MARKED AS FOLLOWS: "FIRE AND SMOKE BARRIER PROTECT ALL OPENINGS". 9. WHERE SKIM COAT IS SPECIFIED IS AN OPTIONAL FINISH. 10. FIRE PARTITIONS SHALL EXTEND FROM THE TOP OF THE FOUNDATION OR FLOOR/ CEILING ASSEMBLY BELOW TO THE UNDERSIDE OF THE FLOOR OR ROOF SHEATHING, SLAB OR DECK ABOVE, OR TO THE FIRE-RESISTANCE- RATED FLOOR/ CEILING ASSEMBLY ABOVE, AND SHALL BE SECURELY ATTACHED THERETO. *FBC 707.5. REFER TO DETAIL ON A-11.00 11. BACKING: WHERE BACKING IS NEEDED IN WALLS WITH RESILIENT CHANNEL, ALL OF THE BACKING SHOULD BE SUPPORTED FROM THE RESILIENT CHANNEL. THIS IS USUALLY ACCOMPLISHED WITH SHEET STEEL THAT IS SCREWED INTO MULTIPLE RESILIENT CHANNEL ROWS.				NOTE: • FOR DRYWALL INSTALLATION REFER TO REQUIREMENTS FROM FBC, ASTM C 840, STANDARD SPECIFICATION FOR APPLICATION AND FINISHING OF GYPSUM BOARD; ASTM C 1396, STANDARD SPECIFICATION FOR GYPSUM BOARD, AND ANY OTHER FBC REFERENCED APPLICABLE CODE OR REGULATION. • FOR STUCCO REFER TO FBC, ASTM C926 AND ASTM 1063 FOR INSTALLATION INSTRUCTIONS			



CORWILARCHITECTS
4210 LAGUNA ST. CORAL GABLES FL 33146
LIC.NO. AA-C002151 T.305.448.7383

PROJECT:



10951 SW 84th ST,
MIAMI-DADE, FLORIDA 33173

OWNER:




161 NW 6th ST, Ste. 1020
Miami, Florida 33136

PHASE:


PERMIT SET

WALL TYPE SCHEDULE (CONT.)

REVISIONS		
Rev #	Revision Description	Date
7	Pre-con RFIs/Coord.	05/03/24
10	Coord./Bulletin #6	09/20/24



SEAL:



THIS DRAWINGS IS THE PROPERTY OF CORWIL ARCHITECTS INC.
UNLESS OTHERWISE PROVIDED FOR BY CONTRACT, THE
CONTENTS OF THIS DRAWINGS ARE CONFIDENTIAL AND
SHALL NOT BE TRANSMITTED TO ANY OTHER PARTY
EXCEPT AS AGREED TO BY THE ARCHITECT/ENGINEERS.

DATE: 5-18-2020
JOB No.: 2019-20
DRAWN BY:MA,CM,JM,JW,FG
APPR BY: AMC
PRINTED: 11/25/2024

A-8.01a